



CONCEPT, NOT FOR FABRICATION

ThermaBrick · github.com/BoujeeEnjinia1701/thermabrick


REV	DESCRIPTION	DATE	BY
P1	First issue: general arrangement of the v0.2 design	2026-09-24	AC




TOP VIEW
Scale 1:20; looking down (along -Z)



FRONT VIEW
Scale 1:20; looking at the front (along +Y)



RIGHT VIEW
Scale 1:20; looking at the right side (along -X)



ISOMETRIC CUTAWAY
Quarter removed, not to scale; seen from the front right and above, about 30 deg elevation

KEY DATA AND NOTES	
STORAGE	210 kg dry silica sand, 18.3 kWh(th) between 150 and 450 °C mean
CHARGE	12 cartridge heaters, 250 W each, 3.0 kW at 240 V; sand and well wall 550 °C max
DISCHARGE	Six 1-1/4 in U-tubes, 1.0 kW rated, 1.5 kW boost; supply air 50 °C via mixing tee
ENVELOPE	1,209 mm dia x 1,462 mm high; about 410 kg; slab floor only
SECTION A-A	Front view is cut on the XZ plane through four heater wells; sand omitted for clarity
SAND LEVEL	571 mm above drum floor; headspace filled with 298 mm AES blanket and stone wool
REFERENCE	TBK-PRC-001 design precis, TBK-CAL-001 sizing, bom/bom.csv

THERMABRICK		github.com/BoujeeEnjinia1701/thermabrick	
General arrangement			
DRAWING NO. TBK-DWG-001		REV P1	SHEET 1 of 1
SCALE 1:20	UNITS mm	PROJECTION 	DATE 2026-09-24
MATERIAL / NOTES Carbon steel drum and pipe; AES blanket and stone wool; galvanized jacket. See bom/bom.csv		DRAWN Amish Chadha	
Licensed CERN-OHL-S-2.0 · Design Molecule Lab · designmolecule.com		Generated from cad/src; do not edit by hand	